


PLAN






SECTION C-C



SECTION A-A



BENCHING TO OBVERT OF PIPE

INLET LENGTH - EKI (m)	MINIMUM DIMENSION A (mm)
1.8	250
2.4	300
3.0	400
3.6	450
4.2	500

NOTES:

- COMPRESSIVE STRENGTH OF CONCRETE AT 28 DAYS TO BE 32MPa.
- 75mm MINIMUM BENCHING TO HALF PIPE HEIGHT TOTAL BENCHING TO OBVERT OF PIPE.
- 100mmØ SUBSOIL DRAINAGE PIPE 3.0m LONG WRAPPED IN FABRIC SOCK TO BE PROVIDED IN PIPE TRENCHES ADJACENT TO INLET **PIPES**
- PROVIDE STEP IRONS WHERE PIT IS DEEPER THAN 1.0m AT 300mm **CENTRES**
- PITS OVER 2.1m IN DEPTH TO BE DESIGNED BY STRUCTURAL **FNGINFFR**
- GRATES SHALL BE BICYCLE SAFE AND HAVE MAXIMUM INLET CAPACITY. ALL GRATES MUST BE APPROVED BY THE CITY'S REPRESENTATIVE.
- REINFORCEMENT TO COMPLY WITH AS 1302, 1303 & 1304.
- 8. DRAINAGE PIPE TO BE MINIMUM 375Ø CLASS 4 REINFORCED CONCRETE PIPE

SCALE 1:50

NOTE: ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE STATED

CITY OF SYDNEY

PITS & PIPES STANDARD GULLY PIT WITH EXTENDED KERB INLET

DRAINAGE Rev Dwg No. Date 01.12.19 ΡG 7.1.1 Approved